



El Paso County Emergency Services District #2

100 S. San Elizario Rd., Suite N
Clint, Texas 79836

Telephone (915) 851-0304 Fax (915) 851-9000

Job Site Location:
El Paso County ESD#2
16001 Socorro Road
Fabens, TX 79838

BID #2019-0403F
Addendum 1
Bid Due Date
April 26th, 2019

El Paso County ESD#2 is actively seeking **Bids** for the following project for our District Office Location Located at 16001 Socorro Road, Fabens Texas 79838...All **Bids** over the amount of \$50,000.00 Dollars, must be submitted in a sealed envelope and must have the Bid number on the envelope. All Bids Must be hand delivered or by certified mail to:
100 S. San Elizario Road Suite N. Clint Texas 79836

POC will be Mario Silva 915-549-3926. msilva@epcountyesd2.org

Construction Specifics. Bathrooms and Gym Remodel....

- Contractor will remove existing shower stalls 1 in women's bathroom and 2 in Men's and repair all shower walls, install 12"x24" wall tiles color is Strata Bianco and shower floor tile 12"x12" Marble Urban Blend at Interceramic Tile store, also to include obscured shower glass doors. And brush nickel faucets.
- Contractor will remove all existing floor tile in both women's and men's bathrooms.
- Contractor will supply and Install new 12"x24" Floor Tiles, in both women's and men's Bathrooms Color is Strata Bianco at Interceramic Tile Store.
- Contractor will Remove all wall tile in both women's and men's bathrooms and install 3"x12" Subway Tile, Craft Fawn Gloss at Emser Tile.
- Contractor will supply and Install 3 each 2'x4' rectangular Aluminum windows in Gym area, to match existing windows on building. install steel framing and drywall, texture on this wall only ...
- Contractor will remove in both Men's and Women's existing bathroom partitions, toilets, sinks, faucets and fixtures..
- Contractor will supply and Install on both Men's and Women's Bathrooms... New Stainless Steel Stall partitions, new toilets and urinals. granite counter tops with new undermount square sinks, brush nickel faucets, and framed mirrors...
- Contractor will remove existing cabinets from Laundry Room, and replace with new wood cabinets, stainless steel deep laundry sink and brush nickel faucet. Also remove floor vinyl tile and supply and install 12"x24" Strata Bianco ceramic tile on floor

All construction must meet ADA and IBC Requirements

Contractor must be Insured and Bonded....Contractor must secure all construction permits. Winning bid must provide proof of workers compensation Insurance and prevailing wages for employees.