



El Paso County Emergency Services District #2

100 S. San Elizario Rd., Suite N
Clint, Texas 79836

Telephone (915) 851-0304 Fax (915) 851-9000

Job Site Location:
El Paso County ESD#2
16001 Socorro Road
Fabens, TX 79838

BID #2019-0403E
Addendum 1
Bid Due Date
April 26th, 2019

El Paso County ESD#2 is actively seeking **Bids** for the following project for our District Office Location Located at 16001 Socorro Road, Fabens Texas 79838...All **Bids** over the amount of \$50,000.00 Dollars, must be submitted in a sealed envelope and must have the Bid number on the envelope. All Bids Must be hand delivered or by certified mail to: 100 S. San Elizario Road Suite N. Clint Texas 79836

POC will be Mario Silva 915-549-3926. msilva@epcountyesd2.org

Construction Specifics. General Construction....

- Contractor will Remove all Kitchen Cabinets and Remove wall to extend Kitchen, also remove mail boxes on walls.
- Contractor will supply and install all base and wall cabinets 16ft x 16ft Kitchen with all New Wood 42" tall upper cabinets and lower base cabinets to height of commercial stove
- Stove Griddle Combination 312,000 BTU's total. ¾ Gas Shut Off. Customer will supply all appliances
- Contractor will supply and Install 4ft x 7ft Center Island with single bowl stainless steel sink with brushed nickel faucet, Can tie in existing plumbing to island.
- Contractor will run gas line to stove and water lines to sinks, Fridge and Dishwasher...Also include running all electrical outlets to garbage disposal, backsplash for small appliances
- Contractor will install range hood with kitchen fire suppression system.
- Contractor will supply and install commercial sink with commercial faucet.
- Contractor will supply and install Granite Countertops along with 3" x 12" Sub-way Tile on the entire backsplash...
- Contractor will remove wall in second office by main entrance to make one single office....
- Contractor will supply and install 7"x36" Ceramic Wood Look Tile and Bullnose Cove Base in Kitchen Floor Area. Norway bronze color at Interceramic tile store.
- Contractor will Remove tile in the main entrance area and grind concrete to Apply Epoxy Finish, will include a 5ft x 5ft. El Paso County ESD # 2..Vinyl Logo to be embedded in floor and covered with the epoxy in the Center of the floor. Also install bullnose ceramic cove base.

All construction must meet ADA and IBC Requirements

Contractor must be Insured and Bonded....Contractor must secure all construction permits. Winning bid must provide proof of workers compensation Insurance and prevailing wages for employees.