



El Paso County Emergency Services District #2

16001 Socorro Road, P.O. Box 265
Fabens, Texas 79838
Telephone: (915) 851-0304
Fax: (915) 851-9000

Job Site Location:

West Valley Fire Department
510 E. Vinton Road
Vinton, TX 79821

BID # 2020-1001-1

Bid DUE Date

September 9, 2020

El Paso County ESD#2 is actively seeking **Bids** for the following project at our West Valley Fire Department located at 510 E. Vinton Road, Vinton TX 79821. **Bids over the amount of \$50,000.00 Dollars, must be submitted in a sealed envelope and must have the Bid number on the envelope.** All **Bids** must be hand delivered to 16001 Socorro Road, Fabens, TX 79838 before 4:00 P.M on the Bid Due Date.

POC will be **Mario Silva** cell: (915) 549-3926 email: msilva@epcountyesd2.org.

Construction specifics: 75 FT x 75 FT Concrete Slab.

- Contractor will level soil area to customer specifications.
- Contractor will build a 3 FT x 3 FT x 3 FT concrete basin.
- Contractor will install PVC conduit for 2 lights.
- Contractor will install (2) 20-inch sono, tubes, and galvanized bolts for light poles (3) FT high from finished concrete.
- Contractor will compact area and prep for concrete.
- Contractor will install #4 rebar @ 18-inch x 18-inch for entire area.
- Contractor will install 4-inch valve and PVC Pipe and connect to existing tank.
- Contractor will install 2 x 2 ¼-inch square tubing poles for fence area and seal ends of piping before installing in concrete.
- Contractor will prep concrete for 180 FT x 6-inch x 6-inch curb pour 4500 PSI concrete at 6-inch thick.
- Contractor will cut expansion joints at 15 FT sections for entire concrete.
- Contractor will install 4 FT x 8 FT x 11-gauge steel panels for 180 FT of fencing with 2 X 2 (11) Gauge angle welded to top off post.
- Contractor will fabricate 3 FT x 3 FT, 3 FT deep concrete basin with steel grate.
- Contractor will install and connect new light fixtures to existing electrical circuit.
- Contractor will purchase and install (3) 500 WATT Led equivalent light fixtures, 2 lights on the new light poles and 1 light by pump panel.
- Contractor will install 2 steel light poles (supplied by West Valley Fire Department).
- Contractor will clean up all debris from site.

Any Change Orders must be approved in writing by Chief Esparza.

All construction must meet ADA and IBC Requirements.

Contractor must be Insured and Bonded.

Contractor must secure all construction permits.

Winning bid must provide proof of workers compensation Insurance and prevailing wages for employees.

As per El Paso County ESD #2 Policy, payment will be remitted upon completion of the job.



El Paso County Emergency Services District #2

16001 Socorro Road, P.O. Box 265

Fabens, Texas 79838

Telephone: (915) 851-0304

Fax: (915) 851-9000